





C C

Plan Air Valve (Effluent R/Main)

Typical Details Not to Scale

Items Schedule	(Sewer	R/Main
----------------	--------	--------

DESCRIPTION	DIA(MM)	
Tapping Band (Screwed)	??x50	1
SS Elbow (Screwed) M&F	50	1
SS Nipple (Screwed) M&M	50	1
SS Ball Valve (Screwed) F&F	50	1
SS Elbow (Screwed) M&F	50	1
GFR "Vent Master" Air Valve	50	1
Vent Pipe	-	1
RC Shaft (length to suit)	1050	1
RC Convertor Slab	1050	1
RC Surround & CI Cover	600	1
	Tapping Band (Screwed) SS Elbow (Screwed) M&F SS Nipple (Screwed) M&M SS Ball Valve (Screwed) F&F SS Elbow (Screwed) M&F GFR "Vent Master" Air Valve Vent Pipe RC Shaft (length to suit) RC Convertor Slab	Tapping Band (Screwed) ??x50 SS Elbow (Screwed) M&F 50 SS Nipple (Screwed) M&M 50 SS Ball Valve (Screwed) F&F 50 SS Elbow (Screwed) M&F 50 GFR "Vent Master" Air Valve 50 Vent Pipe - RC Shaft (length to suit) 1050 RC Convertor Slab 1050

Items Schedule (Effluent R/Main)

DESCRIPTION	DIA(MM)	REQD
Tapping Band (Screwed)	200x50	1
Brass Nipple (Screwed) M&M	25	1
Brass Ball Valve (Screwed) F&F	25	1
"Vent-o-Mat" Air Valve (Screwed)	25	1
RC Shaft (length to suit)	1050	1
RC Convertor Slab	1050	1
RC Surround & CI Cover	600	1
	Tapping Band (Screwed) Brass Nipple (Screwed) M&M Brass Ball Valve (Screwed) F&F "Vent-o-Mat" Air Valve (Screwed) RC Shaft (length to suit) RC Convertor Slab	Tapping Band (Screwed) 200x50

NOTES:

- 1. All dimensions are in metres unless otherwise shown.
- 2. Concrete to be 32MPa and in accordance with AS, 1379 and AS, 3600.
- 3. Reinforcement to be in accordance with AS. 4671.
- 4. All flanges to be in accordance with AS. 2129 Table C U.N.O.
- Air Valve marker posts to be installed in accordance with CMDG-W-060.
 Precast Reinforced Concrete Chamber components to be Humes 1050
- Access Chamber Epoxy Jointed or similar approved equivalent.
- RC Convertor Slab, RC Surround & CI Cover to be rotated to provide optimum access to pit.
- RC Surround to be supplied with Cast Iron frame to suit solid Cast Iron bolt down San Sew Cover.
- 9. For details of Vent Pole refer to CMDG-S-035 or CMDG-S-036.
- Where foundation bearing pressure is less than 50 kPa, excavate and replace unsatisfactory material with compacted CBR15 material to the depth ordered by the Works Supervisor.

Counc	
Applical	
Annlice	

APPLICABILITY TABLE							
Council	BSC	CHRC	GRC	IRC	LSC	MRC	RRC
Applicable	Yes	Yes	No	Yes	Yes	Yes	Yes
Applicable	DWG	CMDG-S-057					

REVISIONS		DATE
G	DRAWING REFRENCES UPDATED, STYLE UPDATED	04/2023
F	IRC ADDED	11/2016
Ε	DIMENSIONS EXPRESSED IN MM GRC APPLICABILITY CHANGE	03/2015
D	GRC AND LSC ADDED	09/2014
С	VENT POLE DWG REFERENCE AMENDED	01/2013
R	RRC AMENDMENTS	05/2011

DISCLAIMER.

The authors and sponsoring organisations shall have no liability or responsibility to the user or any other person or entity with respect to any liability, loss or dramage caused or alleged to be caused, directly or indirectly, by the adoption and use of these Standard Drawings including, but nor limited to, any interruption of service, loss of business or anticipatory profits, of consequential damages resulting from the use of these Standard Drawings as the equivalent of, or a substitute for, project-specific design and assessment by an appropriately qualified professional.

Capricorn Municipal Development Guidelines Incorporating:

Banana Shire Council (BSC)
Central Highlands Regional Council (CHRC)
Gladstone Regional Council (GRC)
Livingstone Shire Council (LSC)

Maranoa Regional Council (MRC) Rockhampton Regional Council (RRC) Isaac Regional Council (IRC) AIR VALVES
CONSTRUCTION DETAILS

SEWER	
STANDARD DRAWING	A
CMDG-S-07	2

REV. BCDEFG